


versatile™ 4C Mailbox, 4C13S-11



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.
MAILBOX	MB1	3" H x 12" W x 15" D	11
OUTGOING MAIL	OM2	6-1/2" H x 12" W x 15" D	1

PRODUCT SERIES: **VERSATILE™ 4C FRONT LOAD MAILBOX**

MODEL: 4C13S-11		REV: A
SCALE: NONE	LAST REV DATE: 5/12/2014	
DRAWING NUMBER: 4C13S-11CS	DRAWN BY: AFD	

Notes:

1. This module does NOT meet USPS STD-4C installation specification requirements as shown below:
 - a. At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
 - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - c. No patron (tenant) lock shall be positioned more than 67" AFF.
 - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - e. The USPS Arrow lock shall be positioned 36"-48" AFF.
2. This 4C mailbox is to be used for private applications.
3. The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) - 1 7/8".