


# Versatile™ 4C Mailbox, 4C14S-06



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.
MAILBOX	MB2	6-1'2" H x 12" W x 15" D	6
OUTGOING MAIL	OM2	6-1'2" H x 12" W x 15" D	1

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX

- Notes:
- This module does NOT meet USPS STD-4C installation specification requirements as shown below:
    - At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
    - No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
    - No patron (tenant) lock shall be positioned more than 67" AFF.
    - No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
    - The USPS Arrow lock shall be positioned 36"-48" AFF.
  - This 4C mailbox is to be used for private applications.
  - The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) - 1 7/8".

MODEL	REV
4C14S-06	D
SCALE	LAST REV DATE
NONE	5/16/2014
DRAWING NUMBER	DRAWN BY
4C14S-06CS	AFD