


versatile™ 4C Mailbox, 4CADS-01



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.
MAILBOX	MB2	6-1/2" H x 12" W x 15" D	1
OUTGOING MAIL	OM2	6-1/2" H x 12" W x 15" D	1
PARCEL	PL6	20-1/2" H x 12" W x 15" D	1

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX

Notes:			
1. This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.			
a. At least one customer compartment shall be positioned less than 48" above finished floor (AFF).			
b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.			
c. No patron (tenant) lock shall be positioned more than 67" AFF.			
d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.			
e. The USPS Arrow lock shall be positioned 36"-48" AFF.			
2. This 4C mailbox can also be used for private applications.			
3. The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) - 1/8".			
MODEL 4CADS-01		REV A	
SCALE NONE		LAST REV DATE 5/09/2014	
DRAWING NUMBER 4CADS-01CS		DRAWN BY SDH	