

Alarm.com GSM Quick Installation Instructions

- > Page 2: GE Concord GSM Wireless Gateway Module
- > Page 3: GE Simon GSM Wireless Gateway Module
- > Page 4: GE SimonXT GSM Wireless Gateway Module
- > Page 5: GE NX GSM Wireless Gateway Module



GE Concord Wireless Gateway Module

- 1) Connect the GSM module to the panel according to the provided installation instructions (please refer to page 3 of the installation instructions).
- 2) Make sure all wiring is correct and power up the panel. Connect the battery first and plug in the transformer second (please refer to page 4 of the installation instructions).
- 3) Wait 2-3 minutes for the unit to establish a connection with the GSM network. . LED 1 (red) will stop flashing when a connection is established. If LED 1 does not stop flashing, refer to the "GSM Status LEDs" section in the provided installation instructions (page 5 of the installation instructions).
- 4) LED 4 (green) will flash between 0 and 6 times to indicate signal strength. A minimum of 2 flashes is suggested for proper operation; 3 is the preferred signal strength. If minimal signal strength is not reported, relocate module and repeat this step.
- 5) Once a sufficient signal is obtained, perform the GSM phone test (please refer to page 4 of the installation instructions: "Power Up" Step 5).
- 6) Send test signals and confirm signaling with the central station. Troubleshoot if needed (please refer to page 8 of the installation instructions).



GE Simon Wireless Gateway Module

- 1) Connect the GSM module to the panel according to the provided installation instructions (please refer to page 4 of the installation instructions).
- 2) Make sure all wiring is correct and power up the panel. Connect the battery first and plug in the transformer second (please refer to page 5 of the installation instructions).
- 3) Listen for the panel to say: "Module Okay" upon power up. If this is *not* announced, check the LED's for power. Then check the green & white BUS wires for proper connection. The white wire should be closest to the panel's phone jack when the connector is plugged into the panel circuit board correctly.
- 4) Once "Module Okay" is announced, wait 2-3 minutes for the unit to establish a connection with the GSM network. LED 1 (red) will stop flashing when a connection is established. If LED 1 does not stop flashing, refer to "LED/Key information" section in the provided installation instructions (page 5 of the installation instructions).
- 5) Press the 9/0 key to read the signal strength. The panel will announce "Phone communication XY" (X=number, Y=letter). The number represents the unit's signal strength, which can be between 0-6; the higher the number the better. A minimum of 2 is suggested for proper operation; 3 is the preferred reading. The letter represents the module status or error, if any (please refer to page 5 of the installation instructions for a description of L1's behavior). If minimal signal level is not reported, relocate the module and repeat this step.
- 6) Once a sufficient signal is obtained, perform the GSM phone test (please refer to page 5 of the installation instructions: "Module Registration").
- 7) Send test signals and confirm signaling with the central station. Troubleshoot if needed (please refer to page 7 of the installation instructions).



GE SimonXT Wireless Gateway Module

- 1) Connect the GSM module to the panel according to the provided installation instructions (please refer to page 2 of the installation instructions).
- 2) Make sure all wiring is correct and power up the panel. Connect the battery first and plug in the transformer second (*please refer to page 2 of the installation instructions*).
- 3) Wait 2-3 minutes for the unit to establish a connection with the GSM network. LED 1 (red) will stop flashing when a connection is established. If LED 1 does not stop flashing, refer to "LED Details" section in the provided installation instructions (page 4 of the installation instructions).
- 4) Press the "5" key for 15 seconds to view the Signal strength, module status, & errors, if any. A minimum of 2 signal bars is suggested for proper operation; 3 is the preferred signal strength (please refer to page 5 of the installation instructions for a description of the reports provided by the '5' key). If minimal signal strength is not reported, relocate the module and repeat this step.
- 5) Once a sufficient signal is obtained, perform the GSM phone test (please refer to page 3 of the installation instructions: "GSM Phone Test (Module Registration)").
- 6) Send test signals and confirm signaling with the central station. Troubleshoot if needed (please refer to page 3 of the installation instructions).



GE NX Wireless Gateway Module

- 1) Connect the GSM module to panel according to the provided installation instructions (please refer to page 3 of the installation instructions).
- 2) Make sure all wiring is correct and power up the panel. Connect the battery first and plug in the transformer second (*please refer to page 3 of the installation instructions*).
- 3) Wait 2-3 minutes for the unit to establish a connection with the GSM network. . LED 1 (red) will stop flashing when a connection is established. If LED 1 does not stop flashing, refer to "LED error" descriptions in the provided installation instructions (page 4 of the installation instructions).
- 4) LED 4 (green) will flash between 0 and 6 times to indicate signal strength. A minimum of 2 flashes is suggested for proper operation; 3 is the preferred signal strength. If minimal signal strength is not reported, relocate module and repeat this step.
- 5) Once a sufficient signal is obtained, perform the GSM phone test (please refer to page 3 of the installation instructions: "Power Up" Step 4).
- 6) Send test signals and confirm signaling with the central station. Troubleshoot if needed (please refer to page 5 of the installation instructions).